BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT17870

APPROVED SCHEDULE - B

EE[redacted]P/BBMP/E-PMT/01/2015-16

Construction of Balance Storm Water Drain at Ganaeshwara Layout in Ward No. 09 Vidyaranyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of KODIGEHALLI RAMAKRISHNAPPA SANTOSHKUMAR		
				In Figures		In Words
1	352.80	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	200.0	70560.00	Rupees Two Hundred Only
2	117.60	Providing and filling in foundation with granite/trap broken metal 100mm, and down size, with approved sand including had packing, ramming, watering, including cost of all materials and labour with all lead and lift, etc complete as per specifications and directions of engineer in charge of the work	Cum	1800.0	211680.00	Rupees One Thousand Eight Hundred Only
3	78.40	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5000.0	392000.00	Rupees Five Thousand Only
4	1019.20	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	223.0	227281.60	Rupees Two Hundred Twenty Three Only
5	231.28	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams etc complete as per specifications and directions of engineer in charge of the work	Cum	5800.0	1341424.00	Rupees Five Thousand Eight Hundred Only
6	23.13	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	76499.0	1769421.87	Rupees Seventy Six Thousand Four Hundred Ninety Nine Only
7	627.20	Earthwork excavation (in deposited soil) and filling sides of foundation upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layer by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour etc complete as per specifications and directions of engineer in charge of the work	Cum	202.0	126694.40	Rupees Two Hundred Two Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

2/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of KODIGEHALLI RAMAKRISHNAPPA SANTOSHKUMAR		
				In Figures		In Words
8	317.52	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	68.33	21696.14	Rupees Sixty Eight and Thirty Three Paise Only
					4160758.01	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

12/2/16